

ADDENDUM NO. 6

City of Springfield CITY COMPLEX

Mott MacDonald Project No.: 502100062

August 16, 2024

Plans, Specifications, and Contract Documents shall be amended in the following particulars:

I. QUESTIONS

A. Subsequent to the distribution of Addendum No. 5, the electrical engineer of record has provided additional information to the response to Question No. 99 in Addendum No. 5 regarding the powered gates for the Public Works Building. That additional information is shown in *italics* below:

99. QUESTION: Please provide a specification for the Electric Gate Opening Devices called out on sheet G-04. **RESPONSE:** Contractor shall install Door King model 6500 (or equal) swing gate operators at each of the 4 gate sections. Operators shall be synched to the matching operator, have adjustable auto closure, built in on off switch, magnetic locks, and operate on 115v. Required accessories include exit sensor and card reader access control compatible with the current City of Springfield system. Provide all mounting pads, poles, and hardware required for a complete installation. Additional information on the provision of electric power is forthcoming. *To each gate, provide a 2" conduit from panel LV-PW-A to the first opener and a 2" conduit to the local communication rack in the Public works building. Continue to the second opener for each gate with a 1" Conduit for power and a 1" conduit for control. Additional conduits shall be include as required for card readers outside of each gate. Power circuits shall include 2#8, 1#8G.*

END OF ADDENDUM No. 6

ADDENDUM NO. 6

**City of Springfield
CITY COMPLEX**

Mott MacDonald Project No.: 502100062

August 16, 2024

| |
|---|
| <p>ADDENDUM NO. 6 RECEIVED BY: _____</p> <p>COMPANY NAME: _____</p> <p>DATE: _____</p> |
|---|

*Please return acknowledgement of Addendum No. 6 either by email to:
beverly.stephens@mottmac.com*